
LAMP POLE FOOTING SPECIFICATIONS



- ALL CONCRETE FOOTINGS NEED TO BE INSTALLED WITH TOP OF BASE FLUSH TO SHARED-USE PATH. COMPACTED 3/4-0" CRUSHED ROCK BACKFILL IS REQUIRED AROUND FOOTINGS, 12" ALL DIRECTIONS, REGARDLESS OF SOIL CONDITION TO MAINTAIN PROPER POLE ALIGNMENT.
- 2 ANCHOR BOLT SIZE AND SPACING AS SHOWN CUSTOMER TO SUPPLY (4 PLACES IN TOP) BOLT CIRCLE 10" DIA, 1" X 36" NC GALV STEEL, 3-1/2" BOLT PROJECTION.
- THE AIR GAP, IF ANY EXISTS BETWEEN THE TOP OF THE FOOTING/PEDESTAL AND THE BOTTOM OF THE POLE SHALL BE GROUTED WITH HIGH STRENGTH, NON-SHRINK GROUT, SUCH AS ALCRETE TWENTY MINUTE FAST SETTING GROUT, OR APPROVED EQUAL, MEETING ODOT SSC SECTION 02440.50(b).
- DIRECTIONAL BORING REQUIREMENTS: BLACK HDPE (HIGH DENSITY POLYETHYLENE) DUCT OR SCHEDULE 40 PVC WITH A MECHANICAL CONNECTION (CERTA-LOK OR LIKE MECHANICAL CONNECTION PRODUCT) PROJECT EXTRUDED RED STRIPES (WHICH IS A SPECIFICATION REQUIREMENT). MANDREL TEST OF HDPE PIPE IS REQUIRED AFTER INSTALLATION WITH CITY INSPECTOR PRESENT.
- TRENCH AND ELBOW CONFIGURATIONS, ALL CONDUIT, JUNCTION BOX AND PAD INSTALLATIONS MUST BE INSPECTED PRIOR TO BACKFILLING.

	Shared-Use Path Lighting – Precast Concrete Footing							CITY OF
Γ	DRAWING NO:	RD-1340	DRAFTED BY:	S. SHORTES	REV	DATE	APPR	WILSON
⊦					1	06/2021	ZJW	
ı	FILE NAME:	RD-1340.DWG	APPROVED BY:	Z. WEIGEL				PUBLIC WORKS
ı	SCALE:	NTC	EFFECTIVE DATE:	6/10/2021				PUBLIC WORKS
	SCALE:	NTS	EFFECTIVE DATE:	6/10/2021				

